


Window Wall

4750-RX and 6250-RX INvision™ Unitized Series



Features

- ✓ 4 3/4" or 6 1/4" frame depth
- ✓ Thermally-improved
- ✓ Captured or vertical structural glazed
- ✓ Narrow 2 1/4" sight lines
- ✓ Two-color finish option
- ✓ Pressure-equalized rain screen design
- ✓ Factory or field glazed
- ✓ Screw-spline construction
- ✓ Head, sill and jamb receptors available
- ✓ Exterior sun shades and interior light shelves available
- ✓ High recycled content aluminum framing

Performance

Allowable Air
0.06 cfm/sqft at 6.24 psf
Water
15 psf
NFRC U-Factor
0.35 to 0.64 BTU/hr.sqft.°F
CRF_i
46 to 60
STC
31 to 34 (est)



DISCLAIMER: Wausau Window and Wall Systems takes no responsibility for product selection or application, including, but not limited to, compliance with building codes, safety codes, laws, merchantability or fitness for a particular purpose; and further disclaims all liability for the use, in whole or in part, of this Technical Guide in preparation of project specifications and/or other documents. Technical Guides are subject to change at any time, without notice, and at Wausau's sole discretion. ©2014 Apogee Wausau Group, Inc.